

The Most Affordable Solar Decathlon House. Ever

Dr. Edwin R. Schmeckpeper P.E., Ph.D, Norwich University

Edwin Schmeckpeper, P.E., Ph.D., is the chair of the Department of Civil and Environmental Engineering at Norwich University. Norwich University was the first private school in the United States to offer engineering courses. In addition, Norwich University was the model used by Senator Justin Morrill for the Land-Grant colleges created by the 1862 Morrill Land Grant Act. Prior to joining the faculty at Norwich University, Dr. Schmeckpeper taught at the University of Idaho, the Land-Grant College for the State of Idaho, and worked as an engineer in design offices and at construction sites.

Dr. Michael Puddicombe, Norwich University

Prof. Matthew Paul Lutz, Norwich University

Matthew Lutz is an architect and certified Passive House consultant. In 2007 he became an Assistant Professor in the School of Architecture and Art at Norwich University. He has taught courses in passive environmental design, building systems, materials, and methods, intermediate and upper level design studios, and special study courses focusing on affordable, solar powered, mobile dwellings. In addition to these courses Mr. Lutz has focused on teaching hands-on design/build studios with a multidisciplinary group of faculty.

Mr. Lutz is the faculty leader in Norwich University's entry in Solar Decathlon 2013, and the primary investigator in the U.S. Department of Energy's Solar Decathlon grant to Norwich University. Aligning with this is Mr. Lutz's research interests in mobile, solar powered buildings, and research related to low-income housing alternatives. With teams of faculty he was twice recognized by Virginia Polytechnic Institute and State University with Excalibur Awards for excellence in a comprehensive cross-disciplinary technology-enriched projects that focus on the design and construction of an environmentally sensitive mobile solar-powered dwellings. In 2006 /2007 he was honored with a Faculty Design Award from the ACSA (Association of Collegiate Schools of Architecture) and with a New Faculty Teaching Award from Virginia Polytechnic Institute and State University. In 2010 he was awarded the Charles A. Dana Award from Norwich University for excellence in teaching. Past efforts have resulted in the design and construction of a portable bio-medical research station being used by scientists studying human-animal health issues in the remote Mahale Mountains of Tanzania, and with Jonathan King received an honorable mention from the SEED organization for their work in on the same project.

Mr. Lutz maintains a small consulting practice along side his teaching activities, enjoys doing forest management work, and developing a small farm with his family in East Calais, Vermont.

Dr. Jeffrey R. Mountain Ph.D, P.E., Norwich University

Jeffrey R. Mountain, Ph.D. P.E., is chair of the Mechanical Engineering Department at Norwich University. He has been an engineering educator for over 20 years and has expertise in Mechatronics, CAD and systems design. He has held full time faculty appointments at the University of Arkansas at Little Rock, the University of Illinois at Urbana Champaign, and The University of Texas at Tyler. Prior to his engineering education career, he was heavily involved with the construction industry in the Houston Texas area. He is a registered Professional Engineer and a licensed Master Plumber. Both of these credentials are with the State of Texas and are current. Most of his academic research has focused on engineering and design education. His technical research has focused on microfluidic applications and applied fuzzy logic and he has teaching interests in Mechatronics, HVAC Systems Design, and Sustainable and Alternative Energy Systems. He has published many papers in the conference proceedings of Frontiers in Education, ASME, and ASEE national and regional conferences, as well as in HVAC specific venues, such as the Hot and Humid Climates Symposium.

Dr. John Edward Pattetson, Norwich University

The Most Affordable Solar Decathlon House. Ever.

The Solar Decathlon Competition

The U.S. Department of Energy Solar Decathlon is a competition in which collegiate teams design, build, and operate solar-powered houses that are intended to be cost-effective, energy-efficient, and attractive. The first Solar Decathlon was held in 2002; subsequent competitions took place in 2005, 2007, 2009, 2011, and 2013. The 2013 event took place at the Orange County Great Park, in Irvine California. All previous events took place in Washington D.C.

The Solar Decathlon is intended to educate students and the public about the economic and environmental benefits of energy efficient, solar powered homes. In addition, it serves as a venue to demonstrate the comfort and affordability of homes that combine energy-efficiency with solar energy systems.

Historic Precedent for Affordability as Design Criteria

One of the initiating reasons for the development of the Solar Decathlon is to “demonstrate market-ready technologies that can meet the energy requirements of our activities by tapping into the sun’s power.” With the intent to broaden the integration and acceptance of solar power in residential applications, the Solar Decathlon has involved 112 collegiate teams and 17,000 students from the United States, Canada, and Europe. It is recognized worldwide as force for introducing and exhibiting the most creative, market-ready, residential solar applications. Over its ten-year development, the Solar Decathlon competition organizers have continually adjusted and refined the competition criteria in an effort to keep a fine balance between making the competition solely an exploratory design exercise and a pragmatic, hammer-ready houses.

Although Solar Decathlon 2009 marked the first event that construction cost estimates were produced and published for all twenty teams, construction costs were only of a minor component of the scoring and overall ranking during Solar Decathlon 2009. Competition organizers stated in the 2007¹ ‘Marketability Contest Guidelines’ that, “A key goal of the Solar Decathlon is to help reduce the cost of building-integrated PV systems. Teams build their houses for a target market of their choosing and are asked to demonstrate the potential of their houses to keep costs affordable within that market.”² Whereas teams from previous Solar Decathlon events could design regardless of cost, 2009 teams were introduced to an entirely new design constraint; cost. And while meeting an affordability benchmark based on a specific target market only accounted for a small portion of the total points available within only one-tenth of the total points possible, the introduction of cost indicates that the competition organizers recognized an interest, through public and participant feedback, in seeing more market-ready prototype houses.

Perhaps the introduction of the Marketability Contest in 2009 pointed toward a forthcoming shift in focus from the Solar Decathlon as a design exploration exercise, to a vehicle for mainstreaming residential solar-powered dwellings. The Marketability Contest became the platform to initiate a focus on affordability, which eventually became its own contest worth one-tenth of the overall available points in Solar Decathlon 2011.

While many forces likely contributed toward the development of the Affordability Contest in Solar Decathlon 2011, one possibility may lie in the composition of teams participating and the houses they presented during Solar Decathlon 2009. Although cost was only scrutinized relative to one section of the Marketability Contest, the competition organizers chose to publish costs in four broad categories; below \$250,000, between \$250,000 and \$450,000, between \$450,000 and \$650,000, and between \$650,000 and \$850,000. Thirteen of the twenty houses presented at Solar Decathlon 2009 had an estimated to cost above \$450,000, and all but one house had a cost estimated above \$250,000. The U.S. Census Bureau estimated the median household income in the United States in 2009 at \$50,221.³ Based on this figure, standard metrics for lending used by mortgage lending institutions, average interest rates in 2009, and a 30-year mortgage, sixty-five percent of prototype houses presented would be affordable only to households earning 42% more than the median household income. In fact, to be considered affordable by median income households in the United States, only one house, the one-bedroom, 520 sq.ft., ZeRow House by Rice University, would be considered financially accessible to median income households in the United States.

At the polar opposite end of the cost spectrum at Solar Decathlon 2009 was Team Germany's, one-bedroom, 771 sq. ft. house. Estimated between \$650,000 and \$850,000, the house incorporated a state-of-the art 11.1kW photovoltaic, high-performance vacuum panel insulation, and ultra sophisticated mechanical, plumbing, and electrical systems. In 2009 Team Ontario's one-bedroom, 791 sq.ft. house, whose photovoltaic array outsized Team Germany's array and had an estimated construction cost above \$650,000, was celebrated for its architectural qualities and livability, it failed to address the financial realities of building a house so far out of reach for so many and thus exacerbated the notion that solar powered homes were something intended only for the wealthy.

The dichotomy between Rice University's ZeRow House and Team Germany's house was one trigger that initiated conversations at Norwich University regarding the development of a high performance solar-powered house that could be affordable by households with below median incomes. After visiting Solar Decathlon 2009 faculty and students alike from Norwich University were taken by the underlying message being conveyed by the Solar Decathlon; that high-performance solar-powered homes achievable, but not practical, or attainable.

Unfortunately, due to the scoring rubrics for the competition, the affordability aspect of the competition was often given only superficial consideration. In the 2011 competition, the most affordable house cost \$230 per square foot while the 2011 overall winner's cost exceeded \$380 per square foot. In 2009, while the construction costs were tabulated for each of the entries, affordability was not a direct component of the competition. Prior to 2009, affordability was not officially calculated, and houses such as the 2007 winner had self-reported cost-estimates exceeding \$400,000 for an 800 square foot house (\$500 per square foot).



Figure 1: Norwich University $\Delta T90$ House at 2013 Solar Decathlon Competition

In the 2013 Solar Decathlon Competition the Norwich University $\Delta T90$ house officially placed first in the Affordability Contest, with an estimated cost of \$168,385 for a 994 square foot house (approximately \$170 per square foot), while scoring 100% for the energy balance portion of the competition. The Norwich $\Delta T90$ house was named for the 90°F difference between inside and outside temperatures that residents of Vermont experience each winter.

Although due to the scoring rubric two other schools were officially listed as tied for first place in affordability, at \$234,000, one of these two houses cost 39% more than the Norwich team's house and at \$248,000, the other cost 48% more than Norwich team's house. All other houses in the 2013 Solar Decathlon competition cost more than \$250,000.⁴

Since 2009, when cost estimates became an official component of the Solar Decathlon competition, there has been only one house, the Rice ZEROW house, that had a cost estimate that was less than the 994 square feet 2013 Norwich University $\Delta T90$ house. However, since that house had an area of only 520 square feet, approximately one-half that of the 2013 Norwich University $\Delta T90$ house, its \$229 cost per square foot greatly exceeded the cost per square foot of the Norwich house.

Norwich University's Solar Decathlon Design Philosophy

While the Solar Decathlon Competition is about real estate, its focus on affordability also speaks to practical real estate. An overwhelming number of Vermonters cannot afford a house that meets the target construction costs of the 2011 Solar Decathlon's Affordability Contest, regardless of energy costs. Consequently, for the 2013 Solar Decathlon Competition the Norwich University's $\Delta T90$ house was designed to make it affordable for a household earning 20% to 30% less than Vermont's median income level.

The ΔT90 house is attuned not only to the climactic demands of the Northeast but also to the financial demands of the population that lives there. The bio-based building envelope house is a cost-effective alternative to housing built before 1950, which often had inefficient systems and inadequate insulation. It is designed for a family of three that makes near or below the median income and is intended to be produced in high quantities. The ΔT90 house also has market appeal to retirees who are looking for a structure that is easy to maintain, affordable, does not require a computer to operate and does not have large monthly utility costs. It maximizes comfort, efficiency, and spaciousness through two bedrooms, an office space, and an open living space for lounging, cooking, and gathering—offering a model for affordable and sustainable living.

The structural design fulfilled these goals through effective design and engineering as well as the ability to mass produce the structure. The innovative design was achieved by determining the proper balance between the need for high technology and the practicability and affordability that is inherent to the comprehensive design.

Design Considerations

The ΔT90 house was designed to be low cost from the foundation up. The house was not specifically designed for the Solar Decathlon competition, but was designed for use in Vermont.

The keys to the Minimalist Design Approach were:

- (1) Simplify design
- (2) Use passive vs. active systems
- (3) Reduce systems to minimum required
- (4) Eliminate space wasting mechanical room
- (5) Avoid expensive equipment
- (6) Reduce operational complexity

In examining the different houses at the Solar Decathlon competition, several broad points were evaluated; HVAC/Mechanical Systems, Electrical Systems, and structure. These points selected were designated as a basis for comparing the various elements of the structures, using the Norwich entry as the baseline, being the least expensive of all the structures.

HVAC/Mechanical

In HVAC and mechanical systems, there are always compromises between first costs and high performance. On the Norwich ΔT90 house, long-term performance was the main criterion. Toward this end, the ΔT90 mechanical system integration began with the building envelope itself. By radically slowing heat loss through high-performance building envelope insulation and passive heat-gain strategy, primary annual heating demand could be reduced significantly. This strategy ultimately resulted in reduced size, cost, and complexity of heating and cooling equipment. Use of simple, small, off-the-shelf mechanical systems was made possible simply because the primary architectural investment was placed in the building envelope. .

The heating and cooling system was a ceiling-mounted, ducted mini-split heat pump system with almost zero duct length. Air distribution was accomplished by the use of partially open transoms above the bedroom entry doors, combined with the open concept living, dining and kitchen space. While heat pumps typically do not perform well in extremely cold climates, such as Vermont, the heating load was sufficiently low so that the electric heat strips would be more than adequate to supply heat during the rare occasions when the heat pump became ineffective.

One newly introduced product was used to meet the ventilation needs, while significantly reducing winter heat losses or summertime heat gains. The Lunos e2 heat recovery ventilation system, commonly used in the European market, consists of a matched pair of through-the-wall, axial ventilation fans. The matched pair of fans alternate operating direction; every 70 seconds, one fan is operational as an exhaust while the other reverses and admits ventilation air. Each fan unit has a heat recovery element that recovers 90% of the warm, or cold, air from the conditioned space during the off cycle. The systems use variable speed motors and provide continuous ventilation. Three sets were used in the following manner: a) ventilation across the kitchen/living area, b) ventilation through the two bedrooms, and c) high/low ventilation in the bathroom area. In order to meet the ASHRAE residential ventilation standards, the manufacturer modified the systems so that their highest speed air flow rate was approximately 10% higher than the European factory settings. The continuous movement of cross ventilation air assisted the distribution of conditioned air within the building envelope, while helping to control bathroom and kitchen related humidity. While the installed cost of the three-pair Lunos e2 system was generally expensive, its relatively low power consumption and some first costs were offset by the reduced size of heating and cooling equipment due to losses from high volume on demand ventilation. Ultimately, the Lunos e2 system was cost-comparable to a more conventional ducted heat recovery ventilation unit, which would have consequently lowered ceiling heights, contributed to the overall complexity of the mechanical system, and sacrificed the simplicity of building transportation and deployment.

An operational skylight, combined with an abundance of high-R-value tilt and turn windows, provided significant ventilation and passive cooling capability. The windows and skylight, couple with seasonally tuned shutters, also provided a significant amount of natural lighting throughout the day.

The plumbing and electrical system costs were minimized by the use of a common systems wall, shown on Figure 2. All plumbing supply, waste and vent piping, along with the majority of the high current electrical equipment, was confined to a single 13 foot wall section. The bathroom, including stacked washer/dryer combination, backed up to the kitchen sink and dishwasher. While this consolidation effort reduced first-time costs, it also reduced long-term costs by cutting stand-by losses in transferring hot water from the heat-source to the delivery point.




Figure 2: ΔT90 Common Systems Wall

In addition, the range, water heater, and air handler were all located on, or directly above, this systems wall. While inclusion of the electrical panel on the same wall would have further reduced some of the wiring costs, concerns about the complexity of running main electrical service through primary load-bearing members and compromising useable storage space required that the main electrical panel be placed on a separate wall in the second bedroom.

Concerns about space and safety also influenced the selection of water heating equipment. Typically, a 40 or 50 gallon tank would be specified for a small, single family home. The alternative was to specify a single on-demand water heater to provide the requisite volume and flow rate of adequately heated water. For contest purposes, 15 gallons of 115°F water could be required during a 15 minute period every hour. To ensure adequate volume and temperature, as well as to eliminate standby losses, an instantaneous demand water heater was selected. Since our design specification was based on a Vermont location, the average cold water temperature for the state of Vermont was used to determine temperature rise. The temperature rise, combined with a conservative 1.25 GPM flow rate was used to determine the power requirements for an electrical heat source. As an added benefit, these types of units are compact and wall hung; providing the necessary capacity with a minimal space allocation requirement.

Given the equipment selections and architectural placements made, the area that would have been devoted strictly to mechanical equipment, approximately 9 ft², was available as a utility or storage closet. While not normally considered significant, this represented a 1% increase in useable space to the intended homeowner. And, while 9 ft² is indeed relatively small, it should be noted that the average footprint dedicated to mechanical equipment in Solar Decathlon 2013 houses was approximately 50 ft².

Electrical Systems

The solar electric system chosen for the ΔT90 house was a thin-film amorphous CIGS (copper indium gallium selenide) system offered by Solopower, Inc. As shown in Figure 3, the panels are mounted directly to the flat roof. The SoloPower CIGS system offered the maximum wattage per-square-foot available in thin film technology. The reasoning behind choosing a thin-film photovoltaic system was three-fold. One, the Norwich ΔT90 team wanted to show the local

Vermont market that with the deck stacked against it, the $\Delta T90$ house could stay net-zero annually. While mounting the photovoltaic panels to the flat roof did slightly reduce the possible annual kWh produced, it also allowed the team to show that the overall footprint of the house could be quite small. Again, the $\Delta T90$ house had the smallest foot print of all the houses presented at 2013 Solar Decathlon Competition. This means the Norwich $\Delta T90$ team was able to show that a small solar powered house could fit be integrated in tight urban lots, and be a little less critical of the relation to roof-pitch & solar orientation.

The 5.84 KW photovoltaic system was sized to accommodate the panels being under snow for 120 days annually. This reduced the estimated annual kWh production from approximately 5800 kWh to only 4900 kWh, the intent to show that $\Delta T90$ could, under worst-case-scenario conditions still meet net-zero annual criteria was successful. The Norwich $\Delta T90$ team could then begin to show, in its home market how, under optimum conditions (photovoltaic panels mounted at optimum angle) how energy production could become net-positive. Again, because the primary architectural investment was placed in the building envelope the overall primary energy demand could be reduced, which led to an overall reduction in the size and cost of the photovoltaic system required to meet net-zero criteria.




Figure 3: DT90 Roof Mounted Solar Panels (shown in black)

It should be noted that in Solar Decathlon 2013 the Norwich University $\Delta T90$ house had the smallest solar system present. While the SCI-ARC / CalTech Team had a slightly smaller photovoltaic system at 5,4kW, their overall solar system also included a 1.7kW solar thermal system.

Another reason for the thin film was to avoid the cost and complexity of mounting hardware, along with nearly eliminated wind-loading issues on the panels. Because the thin-film photovoltaic panels can essentially be considered a ‘peel and stick’ system, mounting hardware was eliminated. The team experimented with two types of tape to mount the PV's, including a velcro tape that allows the panels to be removed. While the velcro tape proved slightly more expensive, it allows for later re-configuration or replacement of the panels.

The thin-film photovoltaic panels also offered super reduction in weight and a streamlined profile. The entire ΔT90 building, complete with tools, safety gear, furniture, mechanical equipment, photovoltaic equipment was shipped as a complete, ready to assemble, package. The solar system, being completely building integrated, was shipped on the roof of the house, and is painfully simple to get up and running after the house modules are placed on its foundation. Once the building modules are installed on the foundation, the photovoltaic system can be operable in just two hours with the help two technicians. Critical to the design criteria was to make the building come together easily at the competition, which translated into reduced labor costs.

The structure of the roof was carefully considered for the snow loads experienced in Vermont and was an opportunity to fully integrate the photovoltaic array with the rectilinear form of the ΔT90 house. The photovoltaic array, lying flat on the roof, was intentionally sized to accommodate an average of one-hundred and twenty days of annual snow coverage.

The decision to integrate a thin-film amorphous CIGS photovoltaic array on the roof was a bold move, and one that effectively removes the ‘solar hardware’ from the visual presence of the house. The ΔT90 house is ultra-energy efficient due to the 6kW building integrated PV Array and high performance building insulation. The occupants of the ΔT90 House will enjoy zero utility costs from heating, cooling, and household electricity thanks to energy produced by the solar array

The electrical solar panels were installed on the low sloped roof prior to shipping, with the inverter mounted on the exterior north side of the structure. This allowed the structure to be delivered intact and ready for connection. By installing the solar panels directly on the roof, there was no need for expensive racks to support the solar panels. This eliminated the need to erect the racks at the competition site, reduced the wind loads on the building structure, and resulted in the solar panels not being visible to pedestrians. In contrast to the simple and inexpensive design used by the ΔT90 House, a typical competitor’s design for the racks to support the solar panels is shown in Figure 4. This design includes hollow structural steel columns, steel base plates, and steel wide-flange shapes⁵.

One trade-off was made concerning operating costs compared to initial costs; after comparing energy costs to initial costs, it was decided to rely solely on photovoltaic panels for the solar power. A vacuum tube hot water collector system, utilizing heat pipes as the primary heat collector, could have been matched with a 40 gallon storage tank to supply all of the domestic hot water, and possibly augment the space heating needs of the structure deployed in Vermont. However, the first costs were approximately three times the costs associated with the selected electric demand water heater, and some source of space heating would still be required. In addition, to meet the cooling and humidity criteria, even if deployed in Vermont, some air conditioning equipment, and the attendant photovoltaic power capacity, was going to be required; effectively eliminating any substantial photovoltaic panel savings that might have been realized if the vacuum tube collector system was used. The tank, pumps, valves, and fittings also would occupy a significant amount of space that was preferably used for living or domestic storage.




Figure 5: AT90 Foundation Detail (Competition)

In contrast, several of the competing teams used foundations similar to the one shown in Figure 6. This foundation uses a cast-in-place concrete pad, four steel rods, and a manufactured steel pier.⁷




Figure 6: Competitor's Solar Decathlon Foundation

Similar foundations were used in other structures at the competition. In the competition there was a wide variety of foundation systems. The use of steel frames and metal adjustable standards were incorporated in numerous structures. Steel frames were incorporated in mechanisms to assemble the structures and to provide a level foundation. One of the competing structures used a complex system of poured concrete and steel tracks to allow the structures components to move.

Modular Building Structure

In keeping with the concept of mass replication of the structure, the initial construction was completed by Huntington Homes of East Montpelier, Vermont, a modular home builder. They delivered the structure in two modules, which were rough framed, wired, and plumbed. The two modules were insulated and had interior dry-wall, but not flooring, interior paint, light fixtures,

plumbing fixtures, appliances, cabinets, doors, windows, trim, exterior siding, HVAC systems, or solar panels.

As shown in Figure 7, the $\Delta T90$ house utilizes advanced double stud wall framing in order to take advantage of its three key benefits: less material waste, simpler and quicker construction processes, and improved insulation performance. By aligning the window and door openings with the framing members there is an insulation gain with a reduction in thermal bridging throughout the wall envelope. The roof joists, floor joists, and wall studs are vertically in line at 24 inches on center, which creates a simple, yet direct load path to distribute the roof live loads and dead loads uniformly to the ground. The roof construction is more than sufficient to support the average snow load of 60 pounds per square foot (psf) typically found in Vermont.

The walls, floors, and low slope roof are nominally 12" thick. As shown in Figure 8, the exterior walls utilized 2x12 plates with double 2x4 studs (one the interior and one on the exterior) to reduce the thermal bridging potential. The walls were insulated with nearly 12" of dense pack cellulose insulation. The Norwich design did not use any foam insulation; the environmentally friendly dense pack cellulose insulation was used instead. The exterior was sheathed using 7/16" plywood covered with 2" of mineral wool board insulation on the exterior covered with a layer of house wrap. The house wrap and the mineral wool board also provide hydrophobic protection to the exterior envelope. The exterior cedar siding was attached to the walls via 3/4" batten strips.

Also shown in Figure 8, the floor was of 2x12 construction, with 1-1/8" Tongue & Groove OSB on the upper surface and 1/2" pressure treated plywood on the lower surface. The floor was insulated with dense pack cellulose insulation between the 2x12 floor joists.

Finally, as shown in Figure 8, the roof system also utilized 2x12 construction, with 3/4" plywood sheathing on tapered framing to provide the low slope necessary for roof drainage. The roof was topped with 4" of mineral wool board and the voids between 2x12 roof joists filled with dense pack cellulose insulation. The roof was covered with a 1/8" TPO membrane.

Conventional timber framing was used throughout the $\Delta T90$ house. In contrast, more-expensive steel framing or steel framing with concrete floors⁸ was used by several of the competing teams (Figure 9). The exterior cedar siding used on the $\Delta T90$ house was a low cost alternative to the varying exterior finishes used by others (i.e. sheet metal, shingles, stone, etc.). This figure also shows a relatively small amount of insulation being used under the floor. Some structures used a concrete floor system to allow for hydroponic heating systems. The cost of concrete material and the additional weight for shipping were not cost effective in the overall project.




Figure 7: ΔT90 Framing Scheme




Figure 8: ΔT90 Wall Section




Figure 9: Competitor's Floor Detail

On-Site Construction

The Norwich team shipped our entire project (tools, safety gear, furniture, ramps, decks, porches, everything) inside the two modules that made up the ΔT90 house. As shown in Figure 10, the ΔT90 house required only two modules to be placed on a simple temporary foundation. The house installation required only a crane for only a few hours. The solar electric systems were shipped attached to the roof of the house, and were simple to get up and running after the house modules were installed. At the competition, the ΔT90 house was completely operational before some teams had finished using their cranes to unloading all their materials. Other competitors required the entire week before the competition to install their houses. As shown in Figure 11, some houses required seven trucks to bring all the materials.





Figure 10: ΔT90 Building Module Installation Sequence



- NOTES:
- CRANE PREPARES TO LIFT PV AND SOLAR PANELS INTO PLACE
 - PV AND SOLAR PANELS ARE LIFTED INTO PLACE AND FIXED TO THE SUB-STRUCTURE
 - TRUCK 7 WITH 40 FOOT CONTAINER ARRIVES ON SITE. REFER TO 0-101 FOR TRUCK PARKING LOCATION
 - CRANE PREPARES UNLOAD CONTAINER
 - LANDSCAPE SUB-STRUCTURE AND COMPONENTS, WATER TANKS MODULE ARE UNLOADED
 - TRUCK 7 EMPTY LEAVES SITE
 - CRANE PREPARES TO LIFT WATER TANKS MODULE INTO PLACE
 - WATER TANKS MODULE ARE LIFTED INTO PLACE AND CONNECTED WITH HOUSE
 - THE INSTALLATION OF LANDSCAPE SUB-STRUCTURE IS STARTED

Figure 11: Competitor’s Solar Decathlon Installation Showing Truck # 7

Some teams used modular construction similar to the Norwich ΔT90 house while for shipping reasons others used panelized construction. The Norwich team designed the Norwich ΔT90 so that there was no finish work done on site, that all fixtures and appliances were installed before shipping, and the only electrical and plumbing connections were required on-site.

Summary

The simplicity of the design and construction of the Norwich ΔT90 house fulfilled the mission to create a cost effective, reliable, simple and replicable structure. The design of the structure is open to all of varying economic limits. The design is architecturally pleasing as well as well engineered for efficiency. This structure is available to anyone on a commercial basis and is adaptable to differing climate conditions. The structure was specifically designed for the harsh winters of Vermont, but the same insulation qualities that the structure contains to retain heat in

the winter will also assist in retaining cool air in warmer climates. This structure can be placed on differing foundation systems for permanent installation. The original goal to produce a cost effective design also lead to an overall pleasing, efficient structure.

The use of the modular systems was cost effective and allowed for reduction in the duration for the on-site construction. There were no mechanically moving parts to the structure (i.e. the wall systems did not retract, the entire structure did not move on rails, etc.). None of the mechanical or electrical controls required the use of computers. The cost and functionality of the computer based control systems were not found to be cost effective, and they were not found to add to the efficiency of operation of the structure.

The Norwich entry did not require a separate mechanical room. This utilized the floor space with greater efficiency and the reduction of systems reduced the initial costs and maintenance costs. This is directly tied to the mission of the design and to maintain the overall floor space within the maximum requirement of less than 1000 square feet.

Conclusions

In the 2013 the Norwich University ΔT90 house officially placed first for the Affordability Contest of the 2013 Solar Decathlon, with an estimated cost of \$168,385 for a 994 square foot house (approximately \$170 per square foot), while scoring 100% for the energy balance portion of the competition. As shown in Figure 12, all other houses at the 2013 Solar Decathlon Competition were considerably more expensive than the Norwich University ΔT90 house.




Figure 12: 2013 Solar Decathlon - Construction Cost Data⁴

The Norwich University team set a goal before design began to accomplish a high performance home that is affordable to a household earning 20% below median income in Vermont. The ΔT90 house is attuned not only to the climactic demands of the Northeast but also to the financial demands of the population that lives there. The bio-based building envelope house is a cost-effective alternative to housing built before 1950, which often had inefficient systems and inadequate insulation. It is designed for a family of three that makes near or below the median income and is intended to be produced in high quantities. It maximizes comfort, efficiency, and spaciousness through two bedrooms, an office space, and an open living space for lounging, cooking, and gathering—offering a model for affordable and sustainable living.

Design and Construction details were critically important in attaining the team’s cost goals for the house. This paper presented design and construction details of Norwich University ΔT90 house, and compared them to design and construction details of the other houses at the Solar Decathlon Competition. The Norwich University ΔT90 house was the most economical house in the history of the Solar Decathlon Competition.

At the conclusion of the 2013 Solar Decathlon Competition awards ceremony, the Norwich University ΔT90 team was presented with the Bryon Stafford Award of Distinction for being “honest, caring, humble, intelligent, fair, reliable, steadfast, and genuine.” The award is a tribute to Byron Stafford, who served as the event’s site operations manager from the first Solar Decathlon in 2002 until his death in 2013.

After the completion of the 2013 Solar Decathlon Competition, the ΔT90 house was transported to Frank Lloyd Wright’s The Westcott House for use as an education center.

References

- 1 <http://www.nrel.gov/docs/fy04osti/33151.pdf>
- 2 http://www.solardecathlon.gov/past/2007/contest_market_viability.html
- 3 <http://www.census.gov/prod/2010pubs/acsbr09-2.pdf>
- 4 U.S. Department of Energy, Solar Decathlon Competition, Affordability Contest, http://www.solardecathlon.gov/contest_affordability.html, accessed on 01/05/2014
- 5 U.S. Department of Energy, Solar Decathlon Competition, Middlebury College, Construction Drawings, http://www.solardecathlon.gov/past/2013/pdfs/midd_cd.pdf, accessed on 01/05/2014
- 6 U.S. Department of Energy, Solar Decathlon Competition, Norwich University, Construction Drawings, http://www.solardecathlon.gov/past/2013/pdfs/nu_cd.pdf, accessed on 01/05/2014
- 7 U.S. Department of Energy, Solar Decathlon Competition, Team Texas: The University of Texas at El Paso and El Paso Community College, Construction Drawings, http://www.solardecathlon.gov/past/2013/pdfs/tex_cd.pdf, accessed on 01/05/2014
- 8 U.S. Department of Energy, Solar Decathlon Competition, Missouri University of Science and Technology, Construction Drawings, http://www.solardecathlon.gov/past/2013/pdfs/mst_cd.pdf, accessed on 01/05/2014